

## TEST REPORT

<b>Issued To:</b> M/s Doon Infrastructure, 5A, West Rest Camp, Dehradun (U.K.).	<b>Report No.:</b> METCLPL/DDN/09112024/27 <b>Sample Id:</b> 091124/27 <b>Date of Receipt:</b> 09/11/2024 <b>Date of performance of Testing:</b> 09-10/11/2024 <b>Date of Issue of Report:</b> 15/11/2024
<b>Sample Description:</b> Noise Monitoring <b>Sample Quantity:</b> NA <b>Sample Condition:</b> NA <b>Sample Plan &amp; Sampling Method:</b> N/A. <b>Environment Condition (Temp. &amp; Humidity):</b> NA <b>Addition to, Deviation or Exclusion from the Method:</b> NA	<b>Location/Chainage:</b> A1 (LHS) <b>Sampling Period:</b> 09/11/2024 to 10/11/2023 <b>Test Performed at:</b> Site & Lab
<b>Ref. No.:</b> DI/24-25/403 <b>Dated:</b> 07.11.2024 <b>N.O.W.:</b> Construction of 150M Span Double Lane Motor Bridge over Ratmau River in Daluwala-Lalwala Dhanauri Motor Road in District Haridwar under EPC Mode.	

## TEST CERTIFICATE OF NOISE MONITORING

Parameter	Test-Value In dB	Requirement (as per CPCB Guidelines)	Day	Night
Equivalent Noise Level (Day) (6:00 AM to 10:00 PM)	51.5	Limits in dB(A) Leq. Category of Area Zone.  Residential Area	55	45
Equivalent Noise Level (Night) (10:00 PM to 6:00 AM)	43.4			

**Protocol Used:** IS: 9989-1981

**Remark:** Test Reports show quality of 'Noise' as per National Ambient Noise Quality Standard is OK.

\*\*\*\*\*End of Report\*\*\*\*\*



Mr. Rahul Rohilla (Q.M./T.M)

Reviewed & Authorised

- The result listed refer only to the tested samples and applicable parameters endorsement of product is neither inferred nor implied.
- Total liability of our Lab. is limited to the invoiced amount.
- Samples will be destroyed after 30 Days from the date of issue of test report.
- This report is not be reproduced wholly or in part and cannot be used as an evidence in the court of law and should not be used in any advertising media without our special permission in writing.



**TEST REPORT**

<b>Issued To:</b> M/s Doon Infrastructure, 5A, West Rest Camp, Dehradun (U.K.).	<b>Report No.:</b> METCLPL/DDN/09112024/28 <b>Sample Id:</b> 091124/28 <b>Date of Receipt:</b> 09/11/2024 <b>Date of performance of Testing:</b> 09-10/11/2024 <b>Date of Issue of Report:</b> 15/11/2024
<b>Sample Description:</b> Noise Monitoring <b>Sample Quantity:</b> NA <b>Sample Condition:</b> NA <b>Sample Plan &amp; Sampling Method:</b> N/A. <b>Environment Condition (Temp. &amp; Humidity):</b> NA <b>Addition to, Deviation or Exclusion from the Method:</b> NA	<b>Location/Chainage:</b> A2 (RHS) <b>Sampling Period:</b> 09/11/2024 to 10/11/2023 <b>Test Performed at:</b> Site & Lab
<b>Ref. No.:</b> DI/24-25/403 <b>Dated:</b> 07.11.2024 <b>N.O.W.:</b> Construction of 150M Span Double Lane Motor Bridge over Ratmau River in Daluwala-Lalwala Dhanauri Motor Road in District Haridwar under EPC Mode.	

**TEST CERTIFICATE OF NOISE MONITORING**

Parameter	Test-Value In dB	Requirement (as per CPCB Guidelines)	Day	Night
Equivalent Noise Level (Day) (6:00 AM to 10:00 PM)	54.1	Limits in dB(A) Leq. Category of Area Zone.  <b>Residential Area</b>	<b>55</b>	<b>45</b>
Equivalent Noise Level (Night) (10:00 PM to 6:00 AM)	41.1			

**Protocol Used:** IS: 9989-1981

**Remark:** Test Reports show quality of 'Noise' as per National Ambient Noise Quality Standard is OK.

\*\*\*\*\***End of Report**\*\*\*\*\*



Mr. Rahul Roshni (M./T.M)

Reviewed & Authorised

1. The result listed refer only to the tested samples and applicable parameters endorsement of product is neither inferred nor implied.
2. Total liability of our Lab. is limited to the invoiced amount.
3. Samples will be destroyed after 30 Days from the date of issue of test report.
4. This report is not be reproduced wholly or in part and cannot be used as an evidence in the court of law and should not be used in any advertising media without our special permission in writing.