

# M/S. D.S. CONSTRUCTION

385/65, GAUSHALA, MUZAFFARNAGAR (U.P)

पत्रांक:- DS/2025/05/15/02

दिनांक:- 15/05/2025

सेवा में,

अधिशासी अभियन्ता,  
प्रा० ख०, लो०नि०वि०,  
कर्णप्रयाग।

विषय:- पैकेज संख्या 02/BR/RFB/UGRIDP/2023 व 06/BR/RFB/UGRIDP/2023 के सम्बंध में।

मोहद्य,

हमारे द्वारा उपरोक्त दोनों पैकेज की Air Quality Monitoring, Noise Level, soil, and water की Test Reports भेजी जा रही हैं।

जिनकी कॉपी साथ में संलग्न है।

धन्यवाद।

Rakesh Chamoli, Partner

  
Rakesh Chamoli  
Partner

मै० डी०ए० कंस्ट्रक्शन,  
385/65 गुशाला,  
मुज़फ़रनगर।

सहायक अभियन्ता  
प्रान्तीय खण्ड लो०नि०वि०  
कर्णप्रयाग



NARESH CHAMOLI  
Environmental Expert  
FPIU PMT(U.PREPARE)  
Dehradun



# DEVBHOOMI TESTING LABORATORY DEHRADUN

NABL Accredited, Govt. Approved, MSME Registered, & ISO : 9001:2015 & 14001:2015 Certified Laboratory

Neelkanth Enclave, Harhajwala, Telpur Chowk, Shimla By Pass Road, Dehradun 248171

Mobile: +91-7217360360, +91-7579118238, 8859392493, 9760764229

Email: devbhoomilab@gmail.com

## TEST REPORT

Description of Sample: Air Quality Monitoring	Report No.: DTL/DDN/2025/0704/11
Sample Id: 07042025/11	Date of Report: 14/04/2025
Sample Quantity: As per requirement	Date of Sampling: 07/04/2025
Sample Condition: Receipt as OK	Start Date of Testing: 09/04/2025
Sample Plan & Sampling Method: NA	Date of Completion: 14/04/2025
Environment Condition (Temp. & Humidity): NA	
Addition to, Deviation or Exclusion from the Method: NA	
N.O.W : "Construction of 4 No. of Intermediate lane RCC Bridge & Steel Truss in km 3, 7, 11 & 14 at Nandprayag Ghat Motor Road in Karnprayag Chamoli"	
Issued to: M/S D.S Construction I-7 Nehru colony' Dehradun 248001	Page 1 of 1

Location: R.H.S (Km-07)

S. No.	Parameters	Test Value	Requirement as per National Ambient Air Quality Standards CPCB	
			Industrial, Rural & other area	Sensitive Area
1	Particulate Matter (size < 10µm), µg/m³ (24 hrs)	72.7	100 Max.	100 Max.
2	Particulate Matter (size <2.5 µm), µg/m³(24 hrs)	50.50	60 Max.	60 Max.
3	Sulphur Dioxide, µg/m³ (24 hrs.)	28.7	80 Max.	80 Max.
4	Oxides of Nitrogen, µg/ m³(24 hrs.)	26.8	80 Max.	80 Max.
5	Carbon Mono Oxide, µg/ m³	ND	02*, 04#	02*, 04#

Protocol Used: IS: 5182 (P-2, 3 & 23), CPCB Guidelines.

Note: ND stands for Non-Detectable.

Note: \* Maximum limits for 8 hourly monitoring, # Maximum limits for 1 hourly monitoring.

\*\*\*\*\*End of Report\*\*\*\*\*

*Hector*  
NAresh CHAMOLI  
Environment Expert  
FPU PWD (U-PREPARE)  
Dehradun

*HP*  
सहायक अभियन्ता  
प्रान्तीय खण्ड लो०निर०नि०  
कर्णप्रदेश

Checked & Issued by  
Authorised Signatory

1. The result listed refer only to the tested sample & applicable parameters endorsement of products is neither inferred nor implied.
2. Total liability of our lab is limited to the invoiced amount.
3. Sample not drawn by lab and sample will be destroyed after 30 days from the date of issue of test report.
4. This report is not be reproduced wholly or in part and cannot be used as an evidence in the court of law and should not be used in any advertising media without our special permission in writing.





# DEVBHOOMI TESTING LABORATORY DEHRADUN

NABL Accredited, Govt. Approved, MSME Registered, & ISO 9001:2015 & 14001:2015 Certified Laboratory  
 Neelkanth Enclave, Harbhajwala, Telpur Chowk, Shimla By Pass Road, Dehradun 248171  
 Mob: +91-7217360360, +91-7579118238, 8859392493, 9760764229  
 Email: devbhoomilab@gmail.com

## TEST REPORT

Description of Sample: Air Quality Monitoring	Report No.: DTL/DDN/2025/0704/12
Sample Id: 07042025/12	Date of Report: 14/04/2025
Sample Quantity: As per requirement	Date of Sampling: 07/04/2025
Sample Condition: Receipt as OK	Start Date of Testing: 09/04/2025
Sample Plan & Sampling Method: NA	Date of Completion: 14/04/2025
Environment Condition (Temp. & Humidity): NA	
Addition to, Deviation or Exclusion from the Method: NA	
N.O.W : "Construction of 4 No. of Intermediate lane RCC Bridge & Steel Truss in km 3, 7, 11 & 14 at Nandprayag Ghat Motor Road in Karnprayag Chamoli"	
Issued to:	Page 1 of 1
M/S D.S Construction I-7 Nehru colony, Dehradun 248001	

Location: L.H.S (Km-14)

S. No.	Parameters	Test Value	Requirement as per National Ambient Air Quality Standards CPCB	
			Industrial, Rural & other area	Sensitive Area
1	Particulate Matter (size < 10µm), µg/m³ (24 hrs)	70.12	100 Max.	100 Max.
2	Particulate Matter (size <2.5 µm), µg/m³(24 hrs)	51.36	60 Max.	60 Max.
3	Sulphur Dioxide, µg/m³ (24 hrs.)	27.0	80 Max.	80 Max.
4	Oxides of Nitrogen, µg/ m³(24 hrs.)	29.80	80 Max.	80 Max.
5	Carbon Mono Oxide, µg/ m³	ND	02*, 04#	02*, 04#

Protocol Used: IS: 5182 (P-2, 3 & 23), CPCB Guidelines.

Note: ND stands for Non-Detectable.

Note: \* Maximum limits for 8 hourly monitoring, # Maximum limits for 1 hourly monitoring.

\*\*\*\*\*End of Report\*\*\*\*\*

rtch

NAresh CHAMOLI  
Environment Expert  
FRU PWD (U-PREPARE  
Dehradun

सहायक अभियन्ता  
प्रान्तीय खण्ड लोगोनोंकी  
कार्यपाली

Checked & Issued by  
Authorised Signatory

- The result listed refer only to the tested sample & applicable parameters endorsement of products is neither inferred nor implied.
- Total liability of our lab is limited to the invoiced amount.
- Sample not drawn by lab and sample will be destroyed after 30 days from the date of issue of test report.
- This report is not be reproduced wholly or in part and cannot be used as an evidence in the court of law and should not be used in any advertising media without our special permission in writing.





# DEVBHOOMI TESTING LABORATORY DEHRADUN

NABL Accredited, Govt. Approved, MSME Registered, & ISO : 9001:2015 & 14001: 2015 Certified Laboratory

Neelkanth Enclave, Harbhajan, Telpur Chowk, Shimla By Pass Road, Dehradun 248171

Mob: +91-7217360360, +91-7579118238, 8859392493, 9760764229

Email: devbhoomilab@gmail.com

## TEST REPORT

Description of Sample: Air Quality Monitoring	Report No.: DTL/DDN/2025/0704/13
Sample Id: 07042025/13	Date of Report: 14/04/2025
Sample Quantity: As per requirement	Date of Sampling: 07/04/2025
Sample Condition: Receipt as OK	Start Date of Testing: 09/04/2025
Sample Plan & Sampling Method: NA	Date of Completion: 14/04/2025
Environment Condition (Temp. & Humidity): NA	
Addition to, Deviation or Exclusion from the Method: NA	
N.O.W : "Construction of 4 No. of Intermediate lane RCC Bridge & Steel Truss in km 3, 7, 11 & 14 at Nandprayag Ghat Motor Road in Karnprayag Chamoli"	
Issued to:	Page 1 of 1
M/S D.S Construction I-7 Nehru colony' Dehradun 248001	

Location: R.H.S (Km-14)

S. No.	Parameters	Test Value	Requirement as per National Ambient Air Quality Standards CPCB	
			Industrial, Rural & other area	Sensitive Area
1	Particulate Matter (size < 10µm), µg/m³ (24 hrs)	72.12	100 Max.	100 Max.
2	Particulate Matter (size < 2.5 µm), µg/m³(24 hrs)	52.6	60 Max.	60 Max.
3	Sulphur Dioxide, µg/m³ (24 hrs.)	26.8	80 Max.	80 Max.
4	Oxides of Nitrogen, µg/ m³(24 hrs.)	32.40	80 Max.	80 Max.
5	Carbon Mono Oxide, µg/ m³	ND	02*, 04#	02*, 04#

Protocol Used: IS: 5182 (P-2, 3 & 23), CPCB Guidelines.

Note: ND stands for Non-Detectable.

Note: \* Maximum limits for 8 hourly monitoring, # Maximum limits for 1 hourly monitoring.

\*\*\*\*\*End of Report\*\*\*\*\*

*Nehru*  
**NAresh CHAMOLI**  
 Environment Exp:  
**FNU PWD (U-PREPARE)**  
 Dehradun

*for*  
 सहायक अधिकारी  
 प्रान्तीय खण्ड लोगोनियो  
 कर्मचारी

Checked & Issued by  
 Authorised Signatory

- The result listed refer only to the tested sample & applicable parameters endorsement of products is neither inferred nor implied.
- Total liability of our lab is limited to the invoiced amount.
- Sample not drawn by lab and sample will be destroyed after 30 days from the date of issue of test report.
- This report is not be reproduced wholly or in part and cannot be used as an evidence in the court of law and should not be used in any advertising media without our special permission in writing.





# DEVBHOOMI TESTING LABORATORY DEHRADUN

NABL Accredited, Govt. Approved, MSME Registered, & ISO 19001:2015 & 14001:2015 Certified Laboratory

Neelkanth Enclave, Harbhajwala, Telpur Chowk, Shimla By Pass Road, Dehradun 248171

Mobile +91-7217360360, +91-7579118238, 8859392493, 9760764229

Email: devbhoomilab@gmail.com

## TEST REPORT

Description of Sample: Air Quality Monitoring	Report No.: DTL/DDN/2025/0704/14
Sample Id: 07042025/14	Date of Report: 14/04/2025
Sample Quantity: As per requirement	Date of Sampling: 07/04/2025
Sample Condition: Receipt as OK	Start Date of Testing: 09/04/2025
Sample Plan & Sampling Method: NA	Date of Completion: 14/04/2025
Environment Condition (Temp. & Humidity): NA	
Addition to, Deviation or Exclusion from the Method: NA	
N.O.W : "Construction of 4 No. of Intermediate lane RCC Bridge & Steel Truss in km 3, 7, 11 & 14 at Nandprayag Ghat Motor Road in Karnprayag Chamoli"	
Issued to: M/S D.S Construction I-7 Nehru colony Dehradun 248001	Page 1 of 1

Location: L.H.S (Km-11)

S. No.	Parameters	Test Value	Requirement as per National Ambient Air Quality Standards CPCB	
			Industrial, Rural & other area	Sensitive Area
1	Particulate Matter (size < 10µm), µg/m³ (24 hrs)	76.8	100 Max.	100 Max.
2	Particulate Matter (size < 2.5 µm), µg/m³(24 hrs)	51.26	60 Max.	60 Max.
3	Sulphur Dioxide, µg/m³ (24 hrs.)	15.6	80 Max.	80 Max.
4	Oxides of Nitrogen, µg/ m³(24 hrs.)	28.6	80 Max.	80 Max.
5	Carbon Mono Oxide, µg/ m³	ND	02*, 04#	02*, 04#

Protocol Used: IS: 5182 (P-2, 3 & 23), CPCB Guidelines.

Note: ND stands for Non-Detectable.

Note: \* Maximum limits for 8 hourly monitoring, # Maximum limits for 1 hourly monitoring.

\*\*\*\*\*End of Report\*\*\*\*\*

NAresh CHAMOLI  
Environment Expert  
FIRU PWD (U-PREPARE,  
Dehradun

सहायक अभियन्ता  
प्रान्तीय खण्ड लो०निः०नि०  
कर्णपाल

Checked & Issued by  
Authorised Signatory

- The result Listed refer only to the tested sample & applicable parameters endorsement of products is neither inferred nor implied.
- Total liability of our lab is limited to the invoiced amount.
- Sample not drawn by lab and sample will be destroyed after 30 days from the date of issue of test report.
- This report is not be reproduced wholly or in part and cannot be used as an evidence in the court of law and should not be used in any advertising media without our special permission in writing.





# DEVBHOOMI TESTING LABORATORY DEHRADUN

NABL Accredited, Govt. Approved, MSME Registered, & ISO 17025:2017 Certified Laboratory

Neelkanth Enclave, Harbhajwala, Telpur Chowk, Shimla By Pass Road, Dehradun 248171

Mob: +91-7217360360, +91-7579118238, 8859392493, 9760764229

Email: devbhoomilab@gmail.com

## TEST REPORT

Description of Sample: Air Quality Monitoring	Report No.: DTL/DDN/2025/0704/15
Sample Id: 07042025/15	Date of Report: 14/04/2025
Sample Quantity: As per requirement	Date of Sampling: 07/04/2025
Sample Condition: Receipt as OK	Start Date of Testing: 09/04/2025
Sample Plan & Sampling Method: NA	Date of Completion: 14/04/2025
Environment Condition (Temp. & Humidity): NA	Page 1 of 1
Addition to, Deviation or Exclusion from the Method: NA	
N.O.W : "Construction of 4 No. of Intermediate lane RCC Bridge & Steel Truss in km 3, 7, 11 & 14 at Nandprayag Ghat Motor Road in Karnprayag Chamoli"	
Issued to: M/S D.S Construction I-7 Nehru colony' Dehradun 248001	

Location: R.H.S (Km-11)

S. No.	Parameters	Test Value	Requirement as per National Ambient Air Quality Standards CPCB	
			Industrial, Rural & other area	Sensitive Area
1	Particulate Matter (size < 10µm), µg/m³ (24 hrs)	77.8	100 Max.	100 Max.
2	Particulate Matter (size <2.5 µm), µg/m³(24 hrs)	55.4	60 Max.	60 Max.
3	Sulphur Dioxide, µg/m³ (24 hrs.)	17.4	80 Max.	80 Max.
4	Oxides of Nitrogen, µg/ m³(24 hrs.)	29.8	80 Max.	80 Max.
5	Carbon Mono Oxide, µg/ m³	ND	02*, 04#	02*, 04#

Protocol Used: IS: 5182 (P-2, 3 & 23), CPCB Guidelines.

Note: ND stands for Non-Detectable.

Note: \* Maximum limits for 8 hourly monitoring, # Maximum limits for 1 hourly monitoring.

\*\*\*\*\*End of Report\*\*\*\*\*

NAresh CHAMOLI  
Environmental Ex.  
FRU PWD (U-PREPARE,  
Dehradun

सहायक अभियन्ता  
प्रान्तीय खण्ड लोनिंगिं  
कर्पणप्रयास

Checked & Issued by  
Authorised Signatory

- The result listed refer only to the tested sample & applicable parameters endorsement of products is neither inferred nor implied.
- Total liability of our lab is limited to the invoiced amount.
- Sample not drawn by lab and sample will be destroyed after 30 days from the date of issue of test report.
- This report is not be reproduced wholly or in part and cannot be used as an evidence in the court of law and should not be used in any advertising media without our special permission in writing.



Scanned with OKEN Scanner



# DEVBHOOMI TESTING LABORATORY DEHRADUN

NABL Accredited, Govt. Approved, MSMB Registered, & ISO 19001:2015 & 14001: 2015 Certified Laboratory

Neelkanth Enclave, Harbhajanwala, Telpur Chowk, Shimla By Pass Road, Dehradun 248171

Mob: +91-7217360360, +91-7579118238, 8859392493, 9760764229

Email: devbhoomilab@gmail.com

## TEST REPORT

Description of Sample: Air Quality Monitoring	Report No.: DTL/DDN/2025/0704/16
Sample Id: 07042025/16	Date of Report: 14/04/2025
Sample Quantity: As per requirement	Date of Sampling: 07/04/2025
Sample Condition: Receipt as OK	Start Date of Testing: 09/04/2025
Sample Plan & Sampling Method: NA	Date of Completion: 14/04/2025
Environment Condition (Temp. & Humidity): NA	Page 1 of 1
Addition to, Deviation or Exclusion from the Method: NA	
N.O.W : "Construction of 4 No. of Intermediate lane RCC Bridge & Steel Truss in km 3, 7, 11 & 14 at Nandprayag Ghat Motor Road in Karnprayag Chamoli"	
Issued to: M/S D.S Construction I-7 Nehru colony' Dehradun 248001	

Location: L.H.S (Km-03)

S. No.	Parameters	Test Value	Requirement as per National Ambient Air Quality Standards CPCB	
			Industrial, Rural & other area	Sensitive Area
1	Particulate Matter (size < 10µm), µg/m³ (24 hrs)	77.6	100 Max.	100 Max.
2	Particulate Matter (size <2.5 µm), µg/m³(24 hrs)	53.80	60 Max.	60 Max.
3	Sulphur Dioxide, µg/m³ (24 hrs.)	25.6	80 Max.	80 Max.
4	Oxides of Nitrogen, µg/ m³(24 hrs.)	33.8	80 Max.	80 Max.
5	Carbon Mono Oxide, µg/ m³	ND	02*, 04#	02*, 04#

Protocol Used: IS: 5182 (P-2, 3 & 23), CPCB Guidelines.


Note: ND stands for Non-Detectable.

Note: \* Maximum limits for 8 hourly monitoring, # Maximum limits for 1 hourly monitoring.

\*\*\*\*\*End of Report\*\*\*\*\*

  
**NARESH CHAMOLI**  
 Environment Expert  
**FNU PWD (U-PREPARE)**  
 Dehradun

  
**तीर्त्थपक अभियन्ता**  
**पान्तीष राष्ट्र लो०निं०कि०**  
**कर्णप्रयाण**



Checked & Issued by  
Authorised Signatory

1. The result listed refer only to the tested sample & applicable parameters endorsement of products is neither inferred nor implied.
2. Total liability of our lab is limited to the invoiced amount.
3. Sample not drawn by lab and sample will be destroyed after 30 days from the date of issue of test report.
4. This report is not be reproduced wholly or in part and cannot be used as an evidence in the court of law and should not be used in any advertising media without our special permission in writing.



Scanned with OKEN Scanner



# DEVBHOOMI TESTING LABORATORY DEHRADUN

NABL Accredited, Govt. Approved, MSME Registered, & ISO : 9001:2015 & 14001: 2015 Certified Laboratory  
 Neelkanth Enclave, Harbhajanwala, Telpur Chowk, Shilma By Pass Road, Dehradun 248171  
 Mobi +91-7217360360, +91-7579118238, 8859392493, 9760764229  
 Email: devbhoomilab@gmail.com

## TEST REPORT

Description of Sample: Air Quality Monitoring	Report No.: DTI/DDN/2025/0704/17
Sample Id: 07042025/17	Date of Report: 14/04/2025
Sample Quantity: As per requirement	Date of Sampling: 07/04/2025
Sample Condition: Receipt as OK	Start Date of Testing: 09/04/2025
Sample Plan & Sampling Method: NA	Date of Completion: 14/04/2025
Environment Condition (Temp. & Humidity): NA	
Addition to, Deviation or Exclusion from the Method: NA	
N.O.W : "Construction of 4 No. of Intermediate lane RCC Bridge & Steel Truss in km 3, 7, 11 & 14 at Nandprayag Ghat Motor Road in Karnprayag Chamoli"	
Issued to:	Page 1 of 1
M/S D.S Construction l-7 Nehru colony' Dehradun 248001	

Location: R.H.S (Km-03)

S. No.	Parameters	Test Value	Requirement as per National Ambient Air Quality Standards CPCB	
			Industrial, Rural & other area	Sensitive Area
1	Particulate Matter (size < 10µm), µg/m³ (24 hrs)	78.6	100 Max.	100 Max.
2	Particulate Matter (size <2.5 µm), µg/m³(24 hrs)	55.6	60 Max.	60 Max.
3	Sulphur Dioxide, µg/m³ (24 hrs.)	31.2	80 Max.	80 Max.
4	Oxides of Nitrogen, µg/ m³(24 hrs.)	33.6	80 Max.	80 Max.
5	Carbon Mono Oxide, µg/ m³	ND	02*, 04#	02*, 04#

Protocol Used: IS: 5182 (P-2, 3 & 23), CPCB Guidelines.

Note: ND stands for Non-Detectable.

Note: \* Maximum limits for 8 hourly monitoring, # Maximum limits for 1 hourly monitoring.

\*\*\*\*\*End of Report\*\*\*\*\*

*Helen*  
**NAresh CHAMOLI**  
 Environment Expert  
**FPAU PWD (U-PREPARE)**  
 Dehradun

*Arvind*  
 सहायक अभियन्ता  
 प्रान्तीय खण्ड लोगोनिंदि  
 कर्प्रधार

Checked & Issued by  
 Authorised Signatory

- The result listed refer only to the tested sample & applicable parameters endorsement of products is neither inferred nor implied.
- Total liability of our lab is limited to the invoiced amount.
- Sample not drawn by lab and sample will be destroyed after 30 days from the date of issue of test report.
- This report is not be reproduced wholly or in part and cannot be used as an evidence in the court of law and should not be used in any advertising media without our special permission in writing.

